### **Assessment of Existing Trees**

Loyola College Quadrangle Renovations *The Care of Trees, Inc.* March 23, 2005

### General Introduction-

The Loyola Quadrangle contains a mixture of mature "monarch" trees from the original forest as well as planted trees from prior decades. Some of the planted trees are reaching maturity of their own. Most of the younger trees are in very good condition as are a few of the mature trees. A high level of maintenance was evident by the little amount of deadwood in the tree canopy.

Several of the mature trees have decline and dieback over the years caused by a combination of construction damage, soils compaction from foot traffic, and maintenance practices favoring turf management over tree management.

Proposed renovations will provide opportunities to assess longevity and consider the worthiness of trees in design. Some design decisions will allow more growing space as well as the opportunity for restoration measures for trees currently under stress. However, construction activities also provide opportunities for additional damage and impact as well. In order to minimize these impacts it is essential that the following three step process be followed:

- All design elements must be reviewed in relation to the tree environment (defined as the Critical Root Zone);
- 2. All construction elements must be reviewed likewise;
- 3. Based upon the above a plan and prescription for protection and stress reduction measures can be developed.

### **Assessment of Existing Trees**

(Refer to Tree Inventory and Assessment spreadsheet for tree by tree review)

### Assessment Summary:

As noted in the Introduction a great majority of the trees on the Quad are worthy candidates for long term survival given proper management in the design and construction process.

Fortunately, no trees were observed from ground level with structural issues that warrant removal at this point. This is not to say unsound conditions out of sight within trunks or below ground may exist, just that none were evident at this level of assessment. Some of the trees under stress that exhibit potential for shortened life spans are designated for "replacement planting" and are summarized below. One site visit alone is difficult to gauge long term response as mature trees take 3-5 years or more to exhibit stress conditions or to recover from damage.

### Summary of recommendations are as follows:

Consideration for future replacement planting- #7, 8, 12, 14, 22, 23. Major root restoration measures- #1, 2, 6, 10, 12, 14, 19, 23. Moderate root restoration measures- #3, 4, 5, 7, 8, 9, 20, 25, 27-32.

Final decisions to prioritize efforts spent on major restorations vs replacement planting can best be made at a site visit. Budgets for Major Root Restoration Measures will be provided for the Owner's consideration. This spring / early summer would be excellent choices to initiate these treatments. Fall or spring 2006 would be good times for Moderate Restoration Measures if efforts were to be prioritized.

Restoration Recommendations

The following are all restoration procedures for damaged root systems and declining trees. Some are state of the art materials and methods based upon latest research and science in arboriculture. Some are vary basic. Exact prescription for each tree can be developed based upon Owner's priorities and design / construction decisions. Upon request, budgets can be developed for decision consideration.

Cambistat Tree Growth Regulator is a newly recognized material shown to be effective when applied to high impacted trees. It redirects canopy growth over 2-3 years into the close-in root system thus allowing increased absorption of nutrients and moisture during the stress recovery period. Specific methods and dosage is dictated by species and trunk diameter and prescribed by the project forester.

Radial Mulching is a practice of entrenching radial "spokes" in the upper soils out from the tree trunk using Supersonic Air tools (SSAT) and has several objectives: exposes prior root damage to examination; lets the arborist get a "feel" for the soils layers, level of quality, and composition; provides aeration to compacted soils; allows backfill of suitable composted amendments. Width, depth, type of amendments will be prescribed for each tree's situation.

Soil Nutrient Management-

In lieu of installing large mulch beds for trees in turf landscapes in order to increase organic soil composition new science is available. The objective is to transition from a highly bacterial soils make up favoring turf-grass to a highly fungal soil more favorable to mature trees without compromising turf vitality. Both granular and liquid biostimulents along with microbial inoculants and amendments are applied to rebuild and restore proper balance and composition for healthy, stress resistant root systems. Seasonal applications are timed over three years. Soil testing after the second year of treatments determines the need for following years based upon response.

Supplemental Water. This action is for high impact trees of significance during drought times. Based upon the number and size of trees various strategies can be considered to maintain adequate soil moisture during these times. A prescription for the number of gallons and strategy for watering designated trees will be developed. Large mature trees with impacts to root systems require as much as 100- 250 gallons per week during 90 degree days during summer drought times. Periodic inspections by the project forester/ arborist at this time are critical.

Design Elements Impacting the CRZs:

Walkways and Terraces (9-11 & Humanities)-

Where possible, elevating the proposed walks or Terrace sections above grade within the CRZ will allow roots / topsoil to remain with minimal impact. Root Aeration Matting will be specified and installed to meet structural requirements of the walk as well as site conditions for the trees. Construction and installation of the walk will be confined to the proposed walk with temporary tree protection defining the limits. Rubber tracked skid steer or similar low ground pressure equipment to be used.

Grade cuts and fills within Critical Root Zones should be carefully reviewed. Grade fills can be mitigated with prescription for Root Aeration Matting but grade cuts remove roots due to their typically shallow nature (upper 24" of soils).

Retaining Walls-

Review of footers and tiebacks for walls within CRZs is important.

Site Landscape Lighting-

Site lighting pole bases and conduits will be placed for minimal impact to CRZs. Conduit routes will be designed for minimal impact. LP bases within protected CRZs will be root pruned using SSAT and the construction equipment / materials supported by temporary Root Protection Mat during excavation / construction. Conduits within the CRZs will be directionally bored or excavated with SSAT to minimize damage. Temporary tree protection fencing will delineate the access and construction within the FCE. Up-lights or lighted bollards will similarly be reviewed and constructed for minimal impact.

Landscape Elements-

Large root balled trees will be reviewed for locations and number to minimally impact protected CRZs. Planting bed locations are predominantly near buildings away from trees so will not cause issues in preparation.

Sediment / Erosion Control-

Location of proposed silt fence and direction berms if, used, will be reviewed for impact to the protected CRZ. Silt fence within protected CRZs will be installed on grade with bottom pinned to the existing grade and drainage stone placed to hold secure. Tree Protection adjacent to excavation of footers will have silt fence attached. Where silt fence is placed adjacent to RAM or RPM both materials will be pinned together and permanent fills placed to hold in place.

Irrigation-

If proposed, irrigation mains and electrical need to be reviewed with respect to the CRZs also. During drought times even mature trees require sufficient moisture especially those under prior stress. The ability to increase duration within zones of trees to supplement minimal rainfall during drought times is important.

### Construction Elements

**Demolition Procedures** 

Demolition of existing structures, asphalt, walks, or light poles shall follow procedures to minimize impact to root system, trunk, and branches. Prior to demolition the Contractor will review the designated trees, procedures, access, and equipment with the project forester / arborist. Tree protection fence shall be installed prior to demolition. Equipment access, stockpile, and loading will be positioned to not impact root systems. Backfill voids with suitable topsoil on the upper 12-18" and lightly grade to avoid additional compaction for work within protected CRZs.

General Excavation Procedures

Excavation for underground utilities, foundations, and footers adjacent to and impacting critical root zones shall follow the following procedures: Superintendent to review all locations with project forester prior to layout to determine issues of access, overhead clearance, stockpile of spoils, need for special equipment, special arboricultural measures, and timing of layout to allow special preservation and arboricultural measures. Slope management procedures may be needed to control layback adjacent to critical root zones, such as sheeting and shoring, or trench boxes. Superintendent shall notify project forester of layout for final review. Discrepancies between plans and site conditions will be noted. Project forester shall review start up of excavation to insure construction procedures are being followed. Additional root pruning may be necessary by hand should deeper roots of significance be uncovered. During backfill operations the final 18" shall be composed of site topsoil from stockpile or approved off site topsoil to provide a rooting medium for future re-growth. Compaction of this top layer shall be the

minimum necessary for final grading with no vibratory or roller equipment to be used assuming the area is not to be used for structural fills. When excavation operations occur within existing woodlands mulching as a ground cover may be more suitable than turf establishment.

**Tree Protection During Construction** 

Once further design elements are determined specific protection and stress reduction measures can be prescribed.

### Loyola College, Baltimore, MD

# Quandrangle Specimen Tree Inventory / Assessment

22830 Quicksilver Drive	To the second se		121		Very Good	Red Oak	8	13
The Care of Trees, Inc.			3	Dieback, decline, compacted soils, turf, ex, underground utility.				
			-		Poor	Red Oak	44	12
grade.		× ×	66	Dieback, decline, compacted soils, turf, ex. underground utility.				
Demo walk new walk /		1	-		Good	White Oak	30	
Retaining wall		1	4 74	ex. underground utilities.	Good	White Oak	42	10
		×	2	Tip decline, compacted soils, turf,	Vol y Cook	WIIIOW Can	9	0
	×		12	Compacted soils, ex. offices underground.	Very Good	750 mallow	<b>)</b>	
			24	turf.	Fair	Black Gum	16	Φ
	×		×	Different form, compacted soils,		- III Cons	-	1
			22	underground.	Fair	Pin Oak	ת	1
	×		×	Compacted soils, turf, ex. Utilities	0000	White Can	33	6
Glading, letaning war.	-	;	50	underground, ex, walkway.	2		)	
Demo walk, new walk		×		Compacted soils, turf, ex. Utilities				-
Down wolk pow walk		1	100	Turf, ex utilities underground.	Very Good	Willow Oak	14	On
Retaining wall, Terrace.	×		30 :		Good	Japanese Zelkova	ω	4
grading.	>		12			-	(8)	
procedures, paving /	<					Japan God Conto	10	a
Special demolition			15	walk edge.	Good	lananese Zelkova	5	)
procedures, paving /	×			Compacted soils, turf, close to				
Special demolition			40	Carl Con Control	Fair	White Oak	36	N
procedures, paving / grading.		×	n S	buried root flair, compacted soils,				
Special demolition			2	This top good interior growth.		AMILITO COLIS	43	
grading.		×	64	compacted soils, turf, ex. Utilities underground.	m <u>w</u>	White Oak	5	
Special demolition	$\downarrow$						٠	
Elements of Concern	*O	Litter	7 9 6				Clair leter)	
Design / Construction	8 1 C	People	⊸ n	ىر بىر			(Trunk	
Vec Vec	Sement Societion of Needed	_	Critical				88	
Planning Comments	1 7 2	Kecomin		Exisitng Issues / Comments	Assessed Ranking	Common Name	DBH	Tree
	Promised tions Rosed Upon		Prelimin	200				

3/23/2005

# Quandrangle Specimen Tree Inventory / Assessment

3/23/2005

grade. The Care of Trees, Inc.	×		40	growing space.	Fair	Pin Oak	26	<u> </u>
Demo walk, new pavers,	<		ō	growing space.	Good	Pin Oak	12	30
grade.	×		ά	Compacted soils, restricted				
grade.	×		34	growing space.	Good	Pin Oak	23	29
grade.  Demo walk, new pavers,	×		30		Good	Pin Oak	20	28
Demo walk, new pavers,	( )		25		Good	Pin Oak	18	27
Demo walk, new pavers,	×			Compacted soils, restricted	0000	Afficial fory	71	20
	×		18		Good	American Holly	3 0	200
grade.	×		60	Minor decline, compacted soils, ex. Utilites underground.	Fa:	American Elm	40	25
grade.  Demo walk, new pavers.			62	underground.	Good	American Elm	42	24
Demo walk, new pavers,			1	turt, ex underground utilities.	Poor	Black Oak	36	23
		× ×	η <u>.</u>	Decline, dieback, compacted soils,				
		>	70 /	Short lived invasive	Good	Sycamore Maple	18	22
		+	$\neg$		Good	Willow Oak	14	21
			200		Good	White Oak	34	20
	×	>	45	Buried root flare; turt.	Good	White Oak	30	19
		<	20		Very Good	Japanese Zelkova	14	18
			15	underground.	Very Good	Red Oak	10	17
			24	underground.	Very Good	Willow Oak	16	<b>a</b>
			-	Inspect for oak scale insects.	Good	Willow Oak	16	15
			55	turi, ex. underground unity.	-	White Oak	38	14
Demo walk, new walk / grade		×		Dieback, decline, compacted soils,	3			
Design / Construction Elements of Concern	Oplaceri, Norder steel No Restoration No. De. Elle	Ethure Rediccery	Critical Root Zone Radius in Feet		٠	ž.	(Trunk diameter)	
JOS	100					<b>#</b>		8
Planning Comments	The IS	Recommen	£ 4 }	Exisitng Issues / Comments	Assessed Ranking	Common Name	DBH	Tree #

								32							Tree #
								1			ulallieter)	(Trunk			DBH
								TIII Oak	5	PQ.					Common Name
								very cood						9	Assessed Ranking
									Compacted soils, restricted			8	z.	52	Exisitng Issues / Comments
									16		Feet	Radius in	Critical Roof Zone		ary CRZ
			-						×		Turo Manager	Red 190 10851	acert, oestor	Serie Tion Seden	Recommendations Based Upon Assessment
The second secon					And the second section of the second section of the second section second section sect				grade.	Demo walk new pavers.	Elements of Concern	Design / Construction		*	Planning Comments